

Procore Curricula - **Solution**

Exercise #1 - Door Takeoff

Door Type	Door Number	Material	Notes
A	100B	Glass	1 Total
B	104	Glass	6 Total
	108	Glass	
	118	Glass	
	120	Glass	
	123	Glass	
	133	Glass	
C	100a	Hollow-Metal & Glass	1 Total
D	131C	Hollow-Metal & Glass	1 Total
E	102	None	2 Total
	117	None	
F	107	Solid Wood	9 Total
	110A	Solid Wood	
	110B	Solid Wood	
	111	Solid Wood	
	112A	Solid Wood	
	112B	Solid Wood	
	113	Solid Wood	
	121	Solid Wood	
	141	Solid Wood	
G	122	Solid Wood & Glass	6 Total
	124	Solid Wood & Glass	
	125	Solid Wood & Glass	
	126	Solid Wood & Glass	
	134	Solid Wood & Glass	
	135	Solid Wood & Glass	
H	131B	Solid Wood & Glass	1 Total
J	105	Solid Wood & Glass	3 Total
	106	Solid Wood & Glass	
	131A	Solid Wood & Glass	
K	103	Insulated Metal	1 Total
Total			29 Total

Procore Estimating Tool

Exercise #2 - Takeoff - Flooring **SOLUTIONS - APPX QUANTITIES**

<i>Flooring Type</i>	<i>Quantity</i>	<i>Unit</i>	<i>Notes</i>
Carpet Tile	3440	SF	
Sheet Carpet	225	SY	
Ceramic Tile	775	SF	
Sealed Concrete	580	SF	

Procore Estimating Tool

Exercise #3 - Takeoff - Studs & Track **SOLUTIONS - APPX QUANTITIES**

<i>Material</i>	<i>Unit (ea or lf)</i>	<i>Quantity</i>	<i>Notes</i>
Steel Studs: 3'5/8"	EA	473	
Steel Studs: 6"	EA	210	
Track: 3-5/8"	LF	1240	
Track: 6"	LF	560	

Procore Estimating Tool

Exercise #6 - Takeoff - Slab on Grade **SOLUTIONS - APPX QUANTITIES**

<i>Component</i>	<i>Unit</i>	<i>Quantity</i>	<i>Notes</i>
Slab on Grade - Finished Surface Area	SF	7900	
Slab on Grade - Volume	CY	146	

Procore Curricula

Exercise #7 - Estimate Details

Exercise #	Takeoff Description	Cost Code	Item Cost	Labor Hours Per Unit	Labor Markup %
1	Door Type - A	08-100	\$ 475.00	2.50	5%
	Door Type - B	08-100	\$ 475.00	1.75	5%
	Door Type - C	08-100	\$ 325.00	1.75	5%
	Door Type - D	08-100	\$ 325.00	1.75	5%
	Door Type - E	08-100	\$ -	0.00	5%
	Door Type - F	08-100	\$ 300.00	1.75	5%
	Door Type - G	08-100	\$ 350.00	1.75	5%
	Door Type - H	08-100	\$ 350.00	1.75	5%
	Door Type - J	08-100	\$ 350.00	1.75	5%
	Door Type - K	08-100	\$ 350.00	1.75	5%
2	Carpet - Tile	09-600	\$ 4.25	3.00	5%
	Carpet - Sheet	09-600	\$ 14.00	0.55	5%
	Ceramic Tile	09-300	\$ 8.35	4.60	5%
	Sealed Concrete	03-050	\$ 1.35	0.75	5%
3	Steel Stud - 3-5/8"	05-400	\$ 7.75	0.25	5%
	Steel Stud - 6"	05-400	\$ 9.25	6.00	5%
	Steel Track - 3-5/8"	05-401	\$ 1.50	6.00	5%
	Steel Track - 6"	05-402	\$ 1.75	6.00	5%
4	Column Footings-Volume 30"x30"x30"	03-050	\$ 155.00	0.25	5%
	Column Footings-Volume 24"x30"x30"	03-050	\$ 155.00	0.25	5%
	Column Footings-Volume 30"x30"x100"	03-050	\$ 155.00	0.25	5%
	Column Footings-Forming 30"x30"x30"	03-100	\$ 0.44	2.60	5%
	Column Footings-Forming 24"x30"x30"	03-100	\$ 0.44	2.60	5%
	Column Footings-Forming 30"x30"x100"	03-100	\$ 0.44	2.60	5%
5	Bearing Footings-Volume	03-050	\$ 155.00	0.33	5%
	Shear Footings-Volume	03-050	\$ 155.00	0.33	5%
	Column Footings-Volume	03-050	\$ 155.00	0.33	5%
	Bearing Footings-Forming	03-100	\$ 0.44	2.60	5%
	Shear Footings-Forming	03-100	\$ 0.44	2.60	5%
	Column Footings-Forming	03-100	\$ 0.44	2.60	5%
6	Concrete SOG-Volume	03-050	\$ 155.00	0.40	5%
	Concrete SOG-Surface Area (labor for finishing only)	03-100	\$ -	0.10	5%